



**Colindale, Hyde House**



Project	Colindale, Hyde House
Engineers:	Train & Kemp
Date:	2008
Size:	3400m <sup>2</sup>
Specialist Contractor:	Deccon Ltd

The original asphalt parking decks had reached the end of their effective life cycle and with planned redevelopment of the Hyde House complex it was decided to upgrade the waterproofing and aesthetics of the parking facility.

Following surface grinding preparation and heavy duty repairs to the original asphalt the Deckmaster system R was applied in two light reflecting colours to minimise solar gain on the surface and denote the traffic aisles and parking bays.

Each of the bays was numbered for allocation to the occupants.

Deckmaster system R: Was applied to the existing asphalt exposed car park decks and access ramps.