



Cotton Street
Paisley



Project	Cotton Street Paisley
Main Contractor:	McKean & Company (Glasgow) Ltd
Date:	2008
Size:	3,200m ²
Specialist Contractor:	Decon Ltd
Product:	Deckmaster system R

The roof deck was waterproofed using Deckmaster system R. Due to the fast track programme requirements the system comprised, Deckmaster DPM/Bonder, applied onto the newly laid screed and fully blinded with kiln dried quartz, deckmaster membrane applied and blinded with kiln dried quartz and then sealed with Deckmaster UVR Finish.

The DPM/Bonder can be applied to a substrate with a (98% RH value) The system provides optimum crack-bridging properties and excellent abrasion resistance with anti slip properties, it also protects the substrate from Carbon Dioxide and Chloride ingress.