



Washington Square,  
Workington



Project	Washington Square, Workington
Architects:	CDA
Main Contractor:	Thomas Armstrong
Date:	2006
Size:	10,000m <sup>2</sup>
Specialist Contractor:	Tornado Management Ltd
Product:	Deckmaster ID

The new build intermediate deck was waterproofed using Deckmaster ID, the system comprises Deckmaster DPM/Bonder, fully blinded with kiln dried quartz, sealed with Deckmaster Finish. The system provides an excellent abrasion resistance with anti slip properties, it also protects the substrate from Carbon Dioxide and Chloride ingress. There are fast cure options where projects are particularly time sensitive.

Please contact Deckmaster for further details.